Invoice Header

Field Value

Invoice # ETG-INV-2025-05

Date 20 May 2025 **Supplier** Abc private Ltd

Bill To National Grid Authority

132 kV Double-Circuit Transmission Line Project

Payment

Net 30 days **Terms**

Delivery

DDP (Delivered Duty Paid) job site **Terms**

Line-Item Details

#	Item Description	Specification / Notes	Qty	Unit Price (USD)	Line Total (USD)
1	Lattice Transmission Tower	60 m, galvanized steel	8	9 800	78 400
2	ACSR Conductor (Condor)	300 mm², bundled, per km	25 km	3 250	81 250
3	Composite Long-Rod Insulator	120 kN, 132 kV	240	45	10 800
4	Optical Ground Wire (OPGW)	48-core, per km	25 km	1 050	26 250
5	Hardware & Fittings Set	Suspension, tension, spacer dampers	240	18	4 320
6	Installation & Stringing Labor	Turn-key field work	1 lot	35 000	35 000
7	Testing & Commissioning	Line energization & reports	1 lot	12 000	12 000
	Subtotal				248 020
	VAT (13 %)				32 243
	Grand Total				280 263

Grid-System Reference

- **Voltage level:** 132 kV (R-Y-B phase); nominal frequency 50 Hz.
- **Thermal line rating:** 260 MVA per circuit with summer clearance temperature of 75 °C.
- **Total route length:** ≈ 25 km; average span 350 m; ruling span calculated for sagtension charts.
- Grounding & lightning: OPGW doubles as shield wire; tower footing resistance
 ≤ 5 Ω.
- **Protection scheme:** Distance protection (zones 1–3) plus differential busbar protection at both 132 kV substations.
- **SCADA integration:** IEC-60870--5-104 gateway provided for real-time telemetry, breaker status, and PMU data.
- **Environmental compliance:** Towers sited to avoid migratory-bird flyways; insulators specified with silicon rubber sheds for high pollution levels (IEC 61024).
- **Standards followed:** IEEE-605 (substation grounding), IEC-60826 (loading), IEC-60273 (insulators), and ACI-318 for concrete foundations.